

Daily Calibration is REQUIRED to verify proper sensitivity through the use of a known calibration gas. The RSU's gas sensor is tested and calibrated using the manufacturers "Quick Check Calibration Kit", consisting of : 5000 PPM (.5%) Methane gas cylinder GREEN, delivery hose and regulator.

- For accuracy check / calibration should be done in a still air environment
- Turn the RDA 3A on and allow 5-10 minutes for self check
- Assemble Check Kit and purge
- Place hose into gas sensor (about 1/8") on RSU
- Turn gas on and alarm will sound
- If not take screwdriver and turn Alarm Set Point clockwise till alarm sounds
 - Turn back a little and clear sensor of gas, then very slowly turn clockwise till alarm sounds.

NEVER USE C GAS TO TEST/CALIBRATE

Yearly Calibration : Uses the 4000 PPM WHITE cylinder. Done by factory certified tech.

Procedures for Use W.A.P. same as all operations using B Gas Meter

- 1- **The RDA 3A MUST BE CALIBRATED BEFORE USE** using the .5% Methane gas in the Quick Check Kit. **DO NOT USE C GAS!!**
- 2- Place the CMU on the manhole rack or other suitable location
- 3- Plug into AC power source and turn on (allow 5-10 minutes for unit to complete start-up cycle.)
- 4- Reset Alarm Latch Switch
- 5- Take RSU out and lower into work environment (DO NOT SUBMERGE RSU!!!)
- 6- Head height if dry / 1' over if wet allow 2-5 minutes for testing
- 7- If wet pump out and retest
- 8- Test for hazardous voltage with 188A
- 9- Place duct wand hose over gas sensor on RSU and test all ducts and openings
- 10- Stow wand and secure cord to manhole rack with suspension hook
- 11- **RETEST DUCTS BEFORE LIGHTING TORCH**, after breaks & change of shifts

If RSU gets soaked or submerged it will damage or render the gas sensor inoperable !